

PLANILHA - CÁLCULO DE MOVIMENTAÇÃO DE TERRA
RUA
VISCONDE- ESTACA 0 A 12

Estaca	ÁREAS (m²)			SOMA DAS ÁREAS (m²)		SEMI-DISTÂNCIA (m)	VOLUME (m³)	
	Corte	Aterro	Aterro Corrigido	Corte	Aterro		Corte	Aterro
0	0,509	0,151	0,181	0,000	0,000	0,000	0,000	0,000
1	3,084	0,956	1,147	3,593	1,328	10,000	35,930	13,284
2	2,304	1,282	1,538	5,388	2,686	10,000	53,880	26,856
3	1,720	1,009	1,211	4,024	2,749	10,000	40,240	27,492
4	1,276	1,705	2,046	2,996	3,257	10,000	29,960	32,568
5	1,056	0,610	0,732	2,332	2,778	10,000	23,320	27,780
6	0,356	2,410	2,892	1,412	3,624	10,000	14,120	36,240
7	0,000	5,424	6,509	0,356	9,401	10,000	3,560	94,008
8	0,000	3,817	4,580	0,000	11,089	10,000	0,000	110,892
9	1,168	0,000	0,000	1,168	4,580	10,000	11,680	45,804
10	0,048	0,652	0,782	1,216	0,782	10,000	12,160	7,824
11	2,479	0,000	0,000	2,527	0,782	10,000	25,270	7,824
12	3,564	0,000	0,000	6,043	0,000	10,000	60,430	0,000
12+11,54	0,000	0,000	0,000	0,048	0,782	10,000		

	CORTE	ATERRO
ÁREAS	17,564	18,016
VOLUME	310,550	430,572


Vinicius Liedtke Garcia
 Engenheiro Civil
 CREA/RS 212795
 Portão 112/2019

Vinicius Liedtke Garcia
 Crea/RS 212795